BRUHATH BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGARA DIVISION
SCHEDULE B

NAME OF WORK: PROVIDING DRINKING WATER FACILITIES IN CHANDRAPPA BADAVANE AND SURROUNDING AREAS IN WARD NO 16 JALAHALLI.

Sl.No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1853.50	Earthwork in surface excavation in Hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	258.85	Rupees Two Hundred Fifty Eight And Paise Eighty Five Only
2	792.37	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications.	Cum	332.98	Rupees Three Hundred Thirty Two And Paise Ninety Eight Only
3	50.04	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement concrete road.	Cum	714.20	Rupees Seven Hundred Fourteen And Paise Twenty Only
4	116.77	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road.	Cum	400.04	Rupees Four Hundred And Paise Four Only
5	3707.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 50mm nominal OD pipes	Mtr	529.47	Rupees Five Hundred Twenty Nine And Paise Forty Seven Only
6	30.00	Providing and fixing gun metal wheel valve conforming to IS specification of approved make as per directions including all lead and lift etc., complete.- for 50mm dia	Nos	1694.30	Rupees One Thousand Six Hundred Ninety Four And Paise Thirty Only

Executive Engineer-3
KRIDL, BBMP, Bang...

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

7	973.09	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work) - 32mm nominal CD pipes	Mtr	252.97	Rupees Two Hundred Fifty Two And Paise Ninety Seven Only
8	3.73	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 7.5Newton per sqmm (Machine moulded Wirecut bricks) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	12191.93	Rupees Twelve Thousand One Hundred Ninety One And Paise Ninety Three Only
9	463.38	Providing and fixing in position Bib Cock of approved quality 25mm nominal bore - NP including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Nos	252.97	Rupees Two Hundred Fifty Two And Paise Ninety Seven Only
10	556.05	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	89.42	Rupees Eighty Nine And Paise Forty Two Only
11	2249.69	KSRRB M100-4.1. Cost of Haulage Excluding Loading and Unloading KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. Haulage Distance - 10km's	Cum	111.00	Rupees One Hundred Eleven Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned by CamScanner